

Course content

- 1 Introduction
- 2 Performance
- 3 Design
- 4 **Construction**
- 5 Maintenance
- 6 Management
- 7 Investigation & maintenance measure selection
- 8 Safety aspects
- 9 Rehab, improvement and upgrading



4 CONSTRUCTION

4.1 Subgrade preparation

- The subgrade may eventually become that of a higher trafficked unsealed or even a sealed road
- Preparation must therefore be good
 - Clear all vegetation over full road prism width
 - Remove all roots and top soil
 - Rip and shape the subgrade
 - Compact at OMC to at least 90% Mod AASHTO max dry density
 - Check density (Sand replacement ?, Nuclear (with MC correction) or DCP
 - May be highly variable - DCP – more in less time – do compaction trials
 - Smooth and shape with 4% camber
 - Beware problem materials



4 CONSTRUCTION

4.1 Subgrade preparation

- Conventional compaction usually adequate:
- Variable, weak or sandy materials - high energy impact compaction best
- Compaction:
 - Reduces potential for rutting (permanent deformation)
 - Increases shear strength
 - Reduces permeability



4 CONSTRUCTION

4.1 Subgrade preparation

- Formation and drains
 - Formation material must have CBR of at least 5%
 - Not less than 300 mm above NGL in flat terrain
 - Material from side and mitre drains often suitable
 - If not then import from borrow
- Formation must not interfere with natural drainage
- In flat areas formation must be sufficient to cover drainage pipes
- Side and mitre drains must be wide and deep enough to remove all expected water without ponding or erosion



4 CONSTRUCTION

4.1 Subgrade preparation

- Formation materials should preferably be slightly plastic (PI about 4%) to provide stable platform for WC
- It should be spread and compacted to at least 93% Mod (preferably refusal)
- Smoothed and shaped with camber at least the same as the subgrade and more than final wearing course
- Must be smooth to avoid “ponding” of water – NB differential permeabilities
- Lightly scarify before next layer



4 CONSTRUCTION

4.1 Subgrade preparation

- Wearing course usually placed directly on formation
- “Subbase” can be used:
 - if support is weak
 - for large number of heavies
 - for future upgrading



4 CONSTRUCTION

4.2 Material operations

- Location, winning and transportation of materials are the most expensive component of unsealed roads
- Use optimum material from as close to the project as possible
- Material location and selection as described in Sec 3
- Material specifications determined after processing
- Once the material is:
 - Located
 - Proved to be adequate
 - And Admin complete (expropriation, EMP, etc)
- Commission the borrow pit



4 CONSTRUCTION

4.2 Material operations

- Demarcate and excavate
 - Extent of suitable materials must be clearly marked
 - Depth of excavation carefully controlled (less weathered with depth)
 - Cut face downwards through entire depth of usable material
 - Move parallel to face to facilitate mixing
 - Slope floor away to remove precipitation from foot of face
 - Spot the error !



4 CONSTRUCTION

4.2 Material operations

- Mix and stockpile
 - Natural, weathered materials are highly variable
 - Therefore win (preferably with a bulldozer) and stockpile
 - Allows improved mixing and reduction of variability
 - Better control testing
 - Keep stockpiles low to reduce segregation (regular inspections)
 - If segregation is noted, loading must be closely supervised



4 CONSTRUCTION

4.2 Material operations

- Stone removal
 - Optimally done in borrow pit – reduces haulage of waste
 - Grizzly is cheap and portable – slows down production !
 - Does not remove large elongated particles
 - If excessive oversize, rather crush (too much waste)
 - Particularly rounded alluvial gravels – produce fractured faces
 - Increase shear strength
 - New innovations



Screening bucket



4 CONSTRUCTION

4.2 Material operations

- Breaking oversize
 - Typically done with a grid roller on the road
 - Not always successful
 - Good supervision and correct use of roller essential
 - Make use of rolling trials
 - Corestones seldom breakdown adequately – Treton Impact value




4 CONSTRUCTION

4.2 Material operations

- Breaking oversize
 - Two-stage crusher – with screen ?
 - Generally gives improved grading
 - Rockbuster – effective but slow
 - Manual removal – better in borrow pit (little oversize) than on road but needs good team and supervision






4 CONSTRUCTION

4.2 Material operations

- Blending in borrow pit
 - To alter grading or shrinkage product
 - Can be done in BP if sources are close
 - Usually more effective on the road
 - Close supervision of dumping and mixing – correct proportions
 - Dump and spread largest component first
 - Then second component before mixing
 - Grader or recycler





4 CONSTRUCTION

4.2 Material operations

- Adding moisture in borrow pit
 - Most effective method – less transportation of water
 - Reduces segregation during handling
 - Also reduces dustiness – loss and nuisance
 - Makes sense if compaction follows rapidly (< 24 h)
 - Otherwise do conventional moisture addition



4 CONSTRUCTION

4.2 Material operations

- Slaking materials
 - Some mudrocks, basic crystalline materials and tillites
 - Slake rapidly on exposure to the atmosphere
 - Stockpile to achieve the required breakdown (days to weeks)
 - Should be done in BP and not on road – safety hazard
 - Should not use material that disintegrates to fine powder



4 CONSTRUCTION

4.2 Material operations

- Compaction
 - The heavier the plant the better
 - Certain plant is best for certain operations
 - High energy impact compaction
 - Sheepfoot rollers (tamping)
 - Grid rollers
 - Smooth steel-wheeled rollers (vibrating)
 - Pneumatic tyred rollers (PTR)
- More use should be made of “intelligent compaction”



4 CONSTRUCTION

4.2 Material operations

- High energy impact compaction
 - 3, 4 or 5 sided “rollers”
 - Free fall under gravity
 - Very high energy – greater depth affected
 - Material doesn't need to be at OMC



4 CONSTRUCTION

4.2 Material operations


- Sheepsfoot rollers
 - Have protuberances on the drum that exert high stresses and also provide a kneading action
 - Most effective on cohesive soils where voids and pore pressures are expelled
 - Seldom used for wearing course compaction
 - Effective for cohesive subgrades and formations
 - Effective mass can be increased by vibration
 - Use until protuberances “walk out” of layer
- ie, no longer compresses points of contact but travel on layer



4 CONSTRUCTION

4.2 Material operations

- Grid rollers
 - Widely used for compaction of gravel wearing course
 - Particularly when larger particles need to be broken down
 - Ballast to > 12 or 15 tonnes
 - Tow at 8 – 10 km/h with tractor
 - Leave impressions – don't use for final rolling of WC.
 - When breaking down aggregate – mix after breaking.
 - Check condition of grid – square not round



4 CONSTRUCTION

4.2 Material operations

- Smooth steel wheeled rollers
 - Probably most widely used
 - Very effective on well-graded low to medium plasticity gravels
 - Vibration mode effective on 150-200 mm thick layers
 - Smooth surface
 - NB: Careful not to over-vibrate – delamination or crumbling
 - Also formation of shear planes in low cohesion materials



4 CONSTRUCTION

4.2 Material operations

- Pneumatic Tyred Roller (PTR)
 - Useful for final smooth finish on good selected gravels
 - Heavy static (at least 27 to 30 tonnes)
 - No vibration
 - Advantage over smooth steel drum as it does not “bridge” oversize stones
 - Used for slushing



4 CONSTRUCTION

4.2 Material operations

- Traffic management
 - Important that construction traffic does not use newly constructed road excessively
 - If compacted properly, construction vehicles cause more damage than benefit
 - Potholes and ravelling and not compaction
 - If compaction is poor (why?) there may be benefits of controlled trafficking

4 CONSTRUCTION

4.2 Material operations

- Supervision and control
 - Major problem is lack of supervision and control testing
 - Close supervision and control by experienced personnel during borrow pit operations and construction make a big difference
 - Simplified procedure developed for ILO
 - Mainly for labour-based but equally applicable to conventional roads
 - Portable test kit



4 CONSTRUCTION

4.3 Wearing Course Construction

Good construction practice will:

- Provide the correct thickness of material
- Provide adequate compaction
- Provide a smooth finish with a good cross-sectional shape

This will entail the use of tipper trucks, graders and large self-propelled or towed rollers

Can also be done using labour based techniques



4 CONSTRUCTION

4.3.1. Material thickness:

- Design thickness depends on expected gravel loss and regravelling strategy
- Minimum frequency decided by road authority
- Typically between 100 and 150 mm compacted
- May be up to 200 mm for heavy trafficking
- Generally plan to regravel every 7 to 10 years



4 CONSTRUCTION

4.3.1 Material thickness

Material must be dumped at correct spacings to provide required thickness after spreading and compaction


- Need to know bulking factor, truck loads, etc
- If thickness is incorrect management is affected – premature regravelling
- Or thinner layer when regravelled if remainder is too thick
- Both affect budgeting
- Thickness as consistent as possible over the road – limited loss areas
- Can check with DCP after compaction – change in rate in underlying layer

4 CONSTRUCTION


4.3.2 Compaction

Good compaction = tightly bound layer with:

- Good particle interlock
- Minimum permeability
- Maximum strength/stiffness



4 CONSTRUCTION



4 CONSTRUCTION

4.3.2 Compaction

Benefits of good compaction proved in field trials


- Lower roughness and deterioration rate
- Slower gravel loss
- Less dust
- Reduced road user costs



4 CONSTRUCTION

4.3.2 Dry compaction

- Good sustainability practice – saves water
- Thornthwaite's Moisture Index
- Lack of strength due to soil suction – weakly bonded
- Not recommended for wearing courses



4 CONSTRUCTION

4.3.2 Poor compaction

- Low density – moisture sensitive
- Permeable material
- Ravelling and erodible material
- Road that ruts, compacts under traffic, potholes, corrugates, impassable when soaked
- Initial traffic-induced compaction and increased gravel loss affect management



4 CONSTRUCTION

4.3.2 Compaction moisture

- If water is added in the borrow pit, dumping, spreading and compaction should be done in first 24 hours
- Careful project planning and management
- Construction during the wet season helps (additional moisture, less evaporation)
- Good control when using recycling machines



4 CONSTRUCTION

4.3.2 Compaction control

- Try and get refusal (ie maximum density for the plant)
- Not less than 95% Mod AASHTO
- No overcompaction or de-densification
- Compaction meters fitted to plant (IC)
- Slushing can be useful
- PTR on saturated material – pump excess fines
- Thin layer of tightly bound fines at surface



4 CONSTRUCTION

4.3.2 Compaction aids

- Numerous proprietary products available
- Discuss briefly later
- Best to construct trial sections
- Either reduce water or roller passes



4 CONSTRUCTION

4.3.2 Compaction

- Usually starts with a grid roller or sheepsfoot if no oversize
- Then smooth vibrating drum
- Final with PTR
- Depends on availability and economics

4 CONSTRUCTION

4.3.3 Finish and shape

- Roughness has greatest impact on road user costs
- Try and get as smooth a road as possible
- Easier to maintain



4 CONSTRUCTION

4.3.3 Finish and shape

- Construct with adequate camber (4-5%) with definite crown
- Except on horizontal curves (super-elevation)
- Remove large stones
- Discard away from the road – not available to be bladed onto road later
- Good operators can often break down or remove oversize
- Don't "bury" oversize – it soon appears



4 CONSTRUCTION

4.4. Quality control and assurance

- Unsealed roads are often seen as low cost solution to access
- QC and QA are thus often “reduced” to save costs
- Good QC and QA is critical
- Hear later how important it is - roads perform significantly better



4 CONSTRUCTION

4.4. Quality control and assurance

- Properties to be controlled
 - Material quality
 - Stoniness
 - Compaction
 - Layer thickness

4 CONSTRUCTION

4.4. Quality control and assurance

Material quality

- Material is usually natural gravel from shallow borrow pits
- Topsoil is removed and excavation to specified depth
- Natural variation of materials is high
- Quality exacerbated by poor topsoil removal and depth selection
- Stockpiling can assist with reducing this – assists with control testing
- Regular – cheap – don't take short cuts

4 CONSTRUCTION

4.4. Quality control and assurance

Stoniness/ oversize

- Continuous visual inspection by supervisor
- Don't bury
- Significant effect on quality of grader maintenance




4 CONSTRUCTION

4.4. Quality control and assurance

Compaction

- 95% Mod AASHTO usually specified
- Refusal where possible ($\nless 95\%$)
- Rolling trials
- Plot passes against density/strength/DCP etc
- Determine optimum passes for that condition (MC, material, roller, etc)
- Method specification

Rolling trial



4 CONSTRUCTION

4.4. Quality control and assurance

Compaction


- DCP has been successfully used for QC on a number of projects
- Determine required penetration rate – lab, trials
- Use standard method as specified in COLTO Clause 8200
- More tests possible (random)
- Correct specific problems

4 CONSTRUCTION

4.4. Quality control and assurance

Layer thickness

- Standard method – excavation of holes (density)
- DCP identified it if support is dry
- Probe
- Useful before and after (bulking) 25 – 30%
- Statistical analysis



4 CONSTRUCTION

4.5. Labour intensive construction

- Conventionally machine intensive
- High volumes of material – heavy compaction
- Labour has been used successfully (ILO, Gundo Lashu, GDPTRW)
- Must still achieve specified quality
- Must do trial sections



4 CONSTRUCTION

4.5. Labour intensive construction

- Best on narrow roads (< 6 m)
- Generates significant employment in rural communities
- Create small contractors
- May need conventional compaction





4 CONSTRUCTION

4.6. Drainage

- Unsealed roads are totally exposed to elements
- Rainfall can cause severe maintenance problems
- Must have good drainage
- Control moisture in wearing course
 - Surface
 - Sub-surface



4 CONSTRUCTION

4.6. Drainage

Surface water

- Predominantly rainfall
- Infiltration can be limited by :
 - Well compacted tight, surface layer
 - Good shape
 - Leading water from surface to side drains
 - No erosion or scouring
 - Side drains should lead into good mitre drains
 - Far enough away to remove water from road



4 CONSTRUCTION

4.6. Drainage

Surface water



- Distance between mitre drains depends on grade
- Must avoid ponding but not allow water to speed up and erode
- May be made wider (1 – 1.5 m) to reduce flow velocities
- Check dams and structures
- Typically 0.6 m wide in urban areas
- Dispersive soils – 10 to 50 m depending on grade
- Suggested spacings for erodible and clayey materials

4 CONSTRUCTION

4.6. Drainage

Surface water

- Road surface must be raised above surroundings
- No canals



4 CONSTRUCTION

4.6. Drainage

Surface water

- Drains must be deep and wide enough to handle the water
- Dimensions should be such that flow velocities are not excessive
- Wide enough to be maintained (eg, grader vs labour)
- Flat bottomed drains are less likely to erode than V drains
- Erosion protection may be necessary on steeper grades



4 CONSTRUCTION

4.6. Drainage

Surface water

- If prevailing topography allows runoff to disperse naturally, the provision of drains can be minimised.
- Cost savings, reduced erosion, scouring and sedimentation
- The road should not interfere with natural cross drainage, i.e. provide culverts
- Design carefully to cater for the expected water



4 CONSTRUCTION

4.6. Drainage - Subsurface water

- Derived from high groundwater tables (temporary or permanent)
- Occasionally springs may be encountered
- Usually manifested as continuously damp areas (and constant potholes)
- Subsurface drains – expensive and require monitoring and maintenance
- Shallow rockfill embankments better alternative
- Geosynthetic separation layers – advice from suppliers
- Drainage activities are conducive to labour intensive projects



SUMMARY

Good construction critical

Good understanding of principles and supervision is equally important

